RB-11 · Power Outage at the Data Center

Initial Response

Upon detecting the outage, the UPS supports the load for up to 15 minutes. The diesel generator must start automatically within less than 30 seconds; if it fails to start, the on-site DataCenter Monterrey technician must manually ignite it.

Ordered Shutdown

If the generator is unavailable and the UPS drops below 40% load, shut down the test environments first, followed by applications, and finally the databases.

Recovery

Upon restoring power, power up in reverse order: storage, databases, applications, and finally user services. Validate the integrity of the databases before resuming operations.